*Previous references.*

LB 205-11. 1-6.

1914

(Local Boards

File No. 126-14

Serial Nos. 1-2

*Later references.*

Secretary

Present.

14

5/12/14

# GENERAL AND REVENUE SECRETARIAT.

---

*Serial Nos.* 1-2

**Part B. for** September 1914.

---

SUBJECT

Revised estimate for the Construction of a mud a pucka at Baggalli

---

Sl 1. From the President Dist Bd Kolar. no. 195 dy 14/8/14.

Requests sanction for reasons given to a revised estimate for Rs 5134 for the construction of a mud a pucka Khana at Baggalli, Kolar Dist

Sl 2 To do. no 2756 dy 15/9/14. Sanctions the above estimate.

Secretary.

24/9/14

To be preserved permanently.

4/12/24

G. R. S. 58

GPB—4,000—4-7-11

G. R. S. 12]

General and Revenue Secretariat.

LB File No. 126 of 1914.

| Serial No. | |
|---|---|
| | To The Presidt Dt Bd, Kolar<br>No 2736-78 15.9.14 |
| 2 | Sanctions for Rs 3234/- the estimate as now revised in Serial 1 above |

NOTE—Contn. sheet.

GPB—60,000—7-11-13

4. As a further sum of Rs.425 has also been provided in the current year's District Fund Budget, I request that you will be so good as to obtain the early sanction of Government to the revised estimate amounting to Rs.3,234 for the said work, to enable me to get the work completed before the end of the current Official year.

5. The connected records with the revised estimates in duplicate are herewith submitted.

I have the honor to be,

Sir,

Your most obedient servant,

President, District Board,
Kolar District.

K.A.V

Mysore P. W. D. — Kolar Division

Revised estimate of the probable cost of Constructing a 3rd Class Musafer Khana at Bagepalli Kolar District.

| Particulars of Work | No. | Dimensions | | | Contts | Total |
|---|---|---|---|---|---|---|
| **For Block A.** | | | | | | |
| 1 Earth work Excavation | | | | | | |
| Longitudinal walls | 2 | 42 1/8 | 3' | 2 1/2 | 23 1/2 | |
| Side walls | 2 | 17 5/8 | 3 | 2 1/2 | 9 3/4 | |
| Central wall | 1 | 36 3/8 | 3 1/2 | 2 1/2 | 11 3/4 | |
| Intermediate Cross walls | 3 | 7 1/8 | 3 | 2 1/2 | 6 | |
| Steps in front of the Verandah | 1 | 9 3/8 | 2 3/4 | 1 1/2 | 1/2 | |
| Do in rear | 1 | 4 | 3 | 1/2 | 1/4 | |
| Earth filling to the basement level Verandah | 1 | 29 | 8 1/2 | 2 | 18 1/4 | |
| Do room in Verandah | 1 | 8 1/2 | 7 1/2 | 2 | 4 2/3 | |
| Do rooms in rear | 3 | 11 1/2 | 8 1/2 | 2 | 21 2/3 | |
| Earth work work, for Abandoned Foundation | | | | | | |
| Vide 1st 4 items above | | | | | 51 | |
| Total | | | | | 98 1/3 Cyds | 98 1/3 |
| 2 Burnt Stone in Chunam | | | | | | |
| Foundation | | | | | | |
| Longitudinal walls | 2 | 41 3/8 | 2 | 2 | 331 | |
| Side walls | 2 | 18 7/8 | 2 | 2 | 149 | |
| Central wall | 1 | 37 5/8 | 2 1/2 | 2 | 188 | |

C. C.

B Forward

| | | | | | |
|---|---|---|---|---|---|
| Intermediate Cross wall | 3 | 8 1/8 | 2 | 2 | 97 1/2 |
| Steps on Front Verandah | 1 | 9 3/8 | 3 | 1 | 28 |
| Do Do | 1 | 9 3/8 | 2 | 1/2 | 9 1/3 |
| Do Do | 1 | 9 3/8 | 1 | 1/2 | 4 2/3 |
| Steps on Rear | 1 | 4 | 3 | 1 | 12 |
| Do | 1 | 4 | 2 | 1/2 | 4 |
| Do | 1 | 4 | 1 | 1/2 | 2 |
| Basement Longitudinal walls | 2 | 40 5/6 | 1 1/2 | 2 | 245 |
| Side walls | 2 | 19 1/8 | 1 1/2 | 2 | 114 3/4 |
| Central wall | 1 | 37 5/6 | 2 | 2 | 151 1/3 |
| Intermediate Cross walls | 3 | 8 1/2 | 1 1/2 | 2 | 76 1/2 |
| Total | | | | | 1413 |
| Deduct Slate over Retaining wall | 1 | 29 | 1 1/2 | 1/2 | 21 3/4 |
| Sill Slab of doors on Centre wall | 3 | 5 | 2 | 1/2 | 15 |
| Do Do Verandah room | 1 | 5 1/4 | 1 1/2 | 1/2 | 4 |
| Do Do Rear | 1 | 4 1/2 | 1 1/2 | 1/2 | 3 |
| over Cast Iron Steps on South of the Rear door | 1 | 4 | 1 | 1/2 | 2 |
| over Middle & top Steps | 2 | 4 | 1 1/8 | 1/2 | 4 1/2 |
| over the Front Cast Iron Steps | 2 | 9 3/8 | 1 | 1/2 | 4 3/4 |
| over the Middle & top Steps | 2 | 9 3/8 | 1 1/4 | 1/2 | 11 3/4 |
| Total | | | | | 61 |
| Balance | | | | | c/f 1352 |

7

B. Varandah

| | | | | |
|---|---|---|---|---|
| Cross walls | 6 | 9 | $\frac{15\frac{1}{2}+7\frac{1}{2}}{2}$ | 621 |
| Longitudinal walls in Verandah | 2 | 9 | $\frac{15\frac{1}{2}+7\frac{1}{2}}{2}$ | 207 |
| cross walls (one side) | 1 | 8 | $15\frac{1}{2}$ | 124 |
| on another side | 1 | 8 | $8\frac{1}{4}$ | 66 |
| Cross wall of Verandah just opposite the room | 1 | $10\frac{1}{8}$ | $\frac{15\frac{1}{2}+7\frac{1}{2}}{2}$ | 116 |
| Sides of door in the Central wall | 2×3 | $6\frac{1}{2}$ | $1\frac{1}{2}$ | 58 |
| Do- other walls | 2×2 | $6\frac{1}{2}$ | $1\frac{1}{8}$ | 29 |
| Sides of Window | 2×5 | $3\frac{1}{2}$ | $1\frac{1}{8}$ | 39 |
| Total | | | | 2379 |

Deduction

| | | | | |
|---|---|---|---|---|
| Door ways inside & outside | 2×5 | $3\frac{1}{2}$ | $6\frac{1}{2}$ | $227\frac{1}{2}$ |
| Windows | 2×3 | $2\frac{1}{2}$ | $3\frac{1}{2}$ | $52\frac{1}{2}$ |
| Do Recess to be fixed | 2×2 | $3\frac{1}{2}$ | 3 | 42 |
| Total | | | | 322 |
| Balance | | | | 2057 Sft 20.57 |

Wood work (Honne wood)

| | | | | | |
|---|---|---|---|---|---|
| Rafters front & rear | 2×9 | 15 | 3 | 5 | $28\frac{7}{8}$ |
| Do at side | 2 | 15 | 3" | 5" | $3\frac{1}{8}$ |
| High Rafters | 4 | 19 | 8" | 9" | 38 |
| Jack rafters | 2×4 | $11\frac{1}{2}$ | 3" | 5" | $9\frac{7}{12}$ |
| Do | 2×4 | $8\frac{1}{2}$ | 3" | 5" | $7\frac{7}{12}$ |
| Do | 2×4 | $5\frac{1}{2}$ | 3" | 5" | $4\frac{7}{12}$ |
| Do | 2×4 | $3\frac{1}{2}$ | 3" | 5" | $2\frac{7}{12}$ |
| Breastsummer | 1 | 32 | 5" | 7" | $77\frac{7}{9}$ |
| Wall plate of rear wall | 1 | $40\frac{1}{2}$ | 3" | 4" | $3\frac{3}{8}$ |
| Do Side walls | 2 | $21\frac{3}{4}$ | 3" | 4" | $3\frac{7}{8}$ |
| Do at side wall of Room in Verandah | 1 | $10\frac{1}{4}$ | 3" | 4" | 1 |
| Over Central wall | 1 | 20 | 3" | 4" | $12\frac{1}{3}$ |
| Total | | | | | $1133\frac{3}{4}$ Sft $1133\frac{3}{4}$ |

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| Windows | 3 | 2½ | | 3½ | 26¼ | | |
| Do | 2 | 3½ | | 3 | 21 | | |
| Total | | | | | 47 | Sft | 47¼ |
| Gravelling the floor & Consolidation | | | | | | sft | 161 |
| Verandah | 1 | 29⅞ | 10⅞ | 3 | 23¼ | | |
| Room in Verandah | 1 | 9 | 8 | 3" | 2/3 | | |
| Rooms | 3 | 12 | 9 | 3" | 3 | | |
| Total | | | | | 6½ | cft | 6½ |
| Chacolate Painting | | | | | | | |
| Doors & Windows as per | | | | | | | |
| details noted above both side | 2 × 161 | | | | 322 | | |
| For eave boards around | 2 × 140 × ¾ | | | | 210 | | |
| Total | | | | | 532 | Sft | 5·32 |
| Mangalore tiles Roofing | | | | | | | |
| over teak rafters & Complete | | | | | | | |
| Front & Rear | 2 × 43½ + 20 / 2 × 15 | | | | 9·52 | | |
| Sides | 2 × 24¾ / 2 × 15 | | | | 3·72 | | |
| Total | | | | | 13·24 | " | 13·24 |
| Mangalore Ridge tiles set in mortar | | | | | | | |
| Ridge | 1 | 20 | | | 20 | | |
| Hips | 4 | 19 | | | 76 | | |
| Total Rft | | | | | 96 | Rft | 96 |
| Mangalore Ventilating tiles | | | | | | Nos | 4 |
| Jungle wood eave board | 1 | 140 | | (9") | 140 | | |
| Total | | | | | 140 | Rft | 140 |
| Wood oiling to the Rafters | L. Sum | | | | | Sft | 4·50 |
| White washing two coats as per plastering | | | | | | " | 65·92 |
| Removing Brick wall to fix two Doors | | | | | | | |
| Windows | 2 | 3½ | 3 | 1⅛ | 24 | | |
| Total | | | | | | Cft | 24 |

Abstract for constructing a Compound wall for the 3rd class Mussafer Khana at Bagepalli.

11

| Details of work. | Rs | Rate | Quantity | Amount | Total |
|---|---|---|---|---|---|
| 1. Earthwork Excavation. | Cyd. | " 2 " | 3·7 | 8 | |
| 2. B.t. Stone in Chunnam. | cft. | " 3 " | 218· | 40 | |
| 3. B.t. Brick in clay | cft. | " 2 3 | 326. | 46 | |
| 4. Pointing with Chunnam. | Sq: | 1 8 | . 113 | 2 | |
| 5. Plastering with Chunnam | Sq: | 2 8 | . 4·27 | 11 | |
| 6. Coping with B.t. Brick in Chunnam and plastering over. | Rft. | " 4 | . 75· | 19 | |
| 7. Providing Gate. 4'. | L.S. Rupees. | | | 22 | |
| Total. | | | | 148 | 148/= |

Amount Sanctioned Rs. 148/=

D/11—6-14

V. Arjaswami Gn
Executive Engineer,
Kolar Division.

Dtd

# Abstract =

12

| Items of Work | Per | Rate | Quantity | Amount |
|---|---|---|---|---|
| 1. Earthwork. Excavation. | Cd | " 2 " | 98 1/3 | 12 |
| 2. Bt: Stone in Chunnam. | cft. | " 3 " | 13 52 | 2 5 3 |
| 3. Mounta. | cft. | " 2 9 | 275 3/4 | 47 |
| 4. Bt: Brick in clay. | cft. | " 2 3 | 151.3 | 213 |
| 5. Bt: Brick in Chunnam. | cft. | " 3 " | 214 1/4 | 40 |
| 6. Bt: Stone Slab | cft. | " 2 6 | 218 | 34 |
| 7. Pointing with Chunnam. | Sq. | 1 8 . | 2 5 1 | 4 |
| 8. Plastering with Chunnam | Sq: | 2 8 . | 20.57 | 51 |
| 9. Ironmongery work. inclg: oiling. | cft. | 2 12 . | 110 5/6 | 306 |
| 10. Jungle wood doors & Windows. | cft. | 1 . . | 161 | 161 |
| 11. Flooring with grand & consolidating | Cd | " 6 , 6 1/2 | 2 | |
| 12. Mechanic painting | Sq. | 3 . . | 6 32 | 16 |
| 13. Mangalore tile roofing over teak rafters & complete | Sq. | 24 . . | 13.24 | 318 |
| 14. Mangalore ridge tiles Set in lime Mortar | Rft. | " 6 " | 96 | 36 |
| 15. Providing Mangalore ventilating tiles | each | " 2 3 | 24 | 3 |
| 16. Jungle wood cabin board | Sft | . 4 . | 140 | 35 |
| 17. Whitewashing two coat | Sq | . 3 " | 6 5 92 | 12 |
| 18. Removing Burnt Brick used to fix two Window | cft | . . 3 | 24 | |

P. T. C.

| | | |
|---|---|---|
| Total | | 1623 |
| For two blocks | 1623 × 2 | 3086 |
| 15 For Construction of a Compound wall as per detailed estimate attached | | 148 |
| Total Rupees | | 3234/- |

Amount Sanctioned Rs 3084/-

V Byaswamy

Executive Engineer,
Kolar Division.

MC 11 6/14

Dlt

Mysore P.W.D. Department

14

Kalan Division

Revised estimate for constructing a 3rd class Musafir Khana at Bagepalli in Kolar District.

Amount of estimate Rs. 3234/-

V

G.R.S. 28] 1/9

Sanctions the revised Estimate for the Construction of a Musafirkhana at Bagepalli; Kolar Dist.

15

File No. 126 – 14

Serial No. 2

*Diary No. of letter replied to* 1456

*Proceedings of the Government of His Highness the Maharaja of Mysore*

GENERAL AND REVENUE SECRETARIAT.
( L.S. )

Ans Memo to DC. & Tahsildar

READ—

, *the* 191 .

V

---- P.O. no. 6808-9 / LB. 205-11-2 dt 20.3.13

Date of issue 15-9-14

Signed by Mr M. S. Ramachandiah.

Sanctioning an Estimate for Rs 3,084 for the Construction of a musafirkhana at Bagepalli; Kolar Dist.

ORDER THEREON.—No.

S

---- P.O. no. 7192-3 / LB. 205-11-6 dt 11-3-13 expressing the proposal of the resident Dist. to abandon the sinking of a well in the Compound of the Cost Rs. 175 said musafirkhana, which

over.

SUBJECT.

G.S. 15/9/14.

GPB—50,000—1-12-12

had been included in the
Estimate referred to.

Letter no 195 dt 14.8.14 from — Paper under disposal
the Presdt., Dt. Bd., Kolar dt claiming
that in the course of the Construction
of the ~~land~~ buildings on Section
Certain improvements were found
necessary and forwarding ~~for~~
~~the Executive Engineer, Kolar~~
a revised Estimate for Rs 3,234
for the work ~~the excess over~~ adding that
Rs. 425 over the original Estimate
~~being met from the already~~
~~been provided~~ in the current
year's D.F. Budget.

---

order thereon 2736-7 dt 5/12/14 — 9/15-9-14
~~sanctioned and the original~~
~~Estimate is returned~~

the estimate as now revised,
for Rs 3,234/- is sanctioned.

~~Asst Dr Offg Secy~~ 7/9

Dy

The Presdt., Dt. Bd., Kolar returning the Revised Estimate together with records.

" Comptroller with Copy of the abstract Estimate

7 Engs